



ADD ALTERNATE #4 - ADDITIONAL WASH BAY

SCALE: 1" = 10'

ALTERNATE #4 WASH BAY CONSTRUCTION NOTES

- A4-1** EXTEND ROOF LEADER COLLECTOR PIPE. 8" SCHEDULE 40 PVC PIPE WITH MINIMUM 6" COVER.
- A4-2** INSTALL 9" 90° TEE-WAY FITTINGS.
- A4-3** INSTALL 8" CLEANOUT WITH 18" SQUARE, 6" THICK CONCRETE COLLAR.
- A4-4** DELETE 91.67 L.F. OF CURBING SHOWN IN BASE BID.
- A4-5** ADD 8.00 L.F. OF 6" CURB.
- A4-6** DELETE 23.90 L.F. OF CURBING SHOWN IN BASE BID.
- A4-7** DELETE HEAVY DUTY CONCRETE PAVING SHOWN SHADED.
- A4-8** BARRY CRAFT ALUMINUM DOWNSPOUT BOOT. SEE DETAIL SHEET C-304.
- A4-9** PROVIDE 5x5' CONCRETE PAD. 4" PCC CONCRETE OVER 4" COMPACTED CRUSHER RUN.

ISSUED
FOR BIDDING
DATE: 01/05/12

I HEREBY CERTIFY THAT THESE
DOCUMENTS WERE PREPARED OR
APPROVED BY ME, AND THAT I AM A
DULY LICENSED PROFESSIONAL
ENGINEER UNDER THE LAWS OF THE
STATE OF MARYLAND.
LICENSE NUMBER: 30331
EXPIRATION DATE: 09/23/12

PROJECT TITLE

**TCC / SHORE
TRANSIT BUS
MAINTENANCE
FACILITY
PROJECT -
PHASE II**

31955 TRI-COUNTY WAY
SALISBURY
WICOMICO COUNTY, MD

SHEET TITLE

**UTILITIES
PLAN
ADD. ALTERNATE #4
WASH BAY**

FOR PERMITS &
BIDDING

0 5 10 20
SCALE: 1" = 10'

ISSUE BLOCK

NO.	DATE	DESCRIPTION
5	7/20/11	ISSUED FOR BIDDING
4	6/13/11	WICOMICO COUNTY P-4 SUBMISSION
3	5/27/11	WICOMICO COUNTY P-3 SUBMISSION
2	3/31/11	WICOMICO COUNTY P-2 SUBMISSION
1	10/10	WICOMICO COUNTY SUBMISSION

MARK DATE DESCRIPTION

PROJECT NO.: 2009145.00

DATE: 04/29/10

SCALE: AS SHOWN

DRAWN BY: S.D.B. | PROJ. MGR.: J.A.H.

SHEET

C-306

COPYRIGHT 2009